

**NOTICE OF SPECIAL JOINT MEETING
CITY COUNCIL & PLANNING & ZONING COMMISSION
TUESDAY, DECEMBER 2 – 6:00 PM**

NOTICE IS HEREBY GIVEN THAT THE SEABROOK CITY COUNCIL WILL MEET ON **TUESDAY DECEMBER 2, 2014 AT 6:00 PM** IN THE SEABROOK CITY HALL COUNCIL CHAMBERS, 1700 FIRST STREET, SEABROOK, TEXAS, TO DISCUSS, CONSIDER, AND IF APPROPRIATE, TAKE ACTION WITH RESPECT TO THE ITEMS LISTED BELOW.

THIS MEETING WILL BE HELD IN JOINT SESSION WITH THE PLANNING AND ZONING COMMISSION.

THIS FACILITY IS WHEELCHAIR ACCESSIBLE AND ACCESSIBLE PARKING SPACES ARE AVAILABLE. REQUESTS FOR OTHER ACCOMMODATIONS OR INTERPRETIVE SERVICES, MUST BE MADE, 48 HOURS PRIOR TO THIS MEETING. PLEASE CONTACT THE CITY SECRETARY'S OFFICE AT (281) 291-5600 OR FAX (281) 291-5710 FOR FURTHER INFORMATION.

1.0 PUBLIC COMMENTS AND ANNOUNCEMENTS

At this time we would like to listen to any member of the audience on any subject matter, whether or not that item is on the agenda. All comments are limited to a maximum of four minutes for each speaker. In accordance with the Open Meetings Act, members may not discuss or take action on any item that has not been posted on the agenda. When your name is called, please come to the podium and state your name and address clearly into the microphone before making your comments. Thank you.

2.0 SPECIFIC PUBLIC HEARING(S)

ATTACHMENT 1

- 2.1** Request for preliminary approval of a Planned Unit Development (PUD) to create a Senior Living Complex of approximately 269 units on approximately 12.15 acres. (Applicant)

Applicant: William Friedrichs, Jr., 16865 Diana Lane Ste 200, Houston, TX 77058

Owner: CL Repsdorph LLC, 111 E. Jericho TPKE FL2, Mineola, NY 11501

Owner: Jack Hornsby Jr., 406 Lakeshore Drive, El Lago, TX 77586

Owner: James Hussion Jr., 22110 Terrace Gate Lane, Katy, TX 77450-8054

Owner: Charles & Jan Bosone, PO Box 7, Seabrook, TX 77586

Legal Description: Tracts 1F, 1J, 1, 1H, 1G-1, 1G and 13, Repsdorph Partition, Abstract 52 in the Ritson Morris Survey, Harris County Texas. This property is located immediately east of Repsdorph Road and south of Brummerhop Park.


THE CITY COUNCIL RESERVES THE RIGHT TO HEAR ANY OF THE ABOVE DESCRIBED AGENDA ITEMS THAT QUALIFY FOR AN EXECUTIVE SESSION IN AN EXECUTIVE SESSION BY PUBLICLY ANNOUNCING THE APPLICABLE SECTION NUMBER OF THE OPEN MEETINGS ACT, (CHAPTER 551 OF THE TEXAS GOVERNMENT CODE) THAT JUSTIFIES EXECUTIVE SESSION TREATMENT.

CERTIFICATE

I certify that this notice was posted on the bulletin board on or before Wednesday, November 26, 2014 and that this notice will remain posted until the meeting has ended.



Meredith Brant, TRMC
Assistant City Secretary





CITY OF SEABROOK

AGENDA BRIEFING

Date of Meeting: December 2, 2014

Submitter/Requestor: Community Development

Date Submitted: November 21, 2014

Presenter: Sean Landis

Description/Subject:

A request for approval of a Preliminary Planned Unit Development (PUD) to create "Chesapeake Bay Luxury Seniors Community" approximately 13 acre, 269 unit, luxury apartment complex.

Applicant:

WMF Investments (William Friedrichs)

Legal Description: Tracts 1F, 1J, 1, 1H, 1G-1, 1G and 13, Repsdorph Partition, Abstract 52 in the Ritson Morris Survey, Harris County Texas.

This property is located immediately east of Repsdorph and south of Brummerhop Park.

Request: The applicant is requesting the aforementioned property be granted approval of a preliminary Planned Unit Development (PUD) Overlay.

Purpose/Need: Policy Issue ☒ Administrative Issue ☐

The purpose of the preliminary Planned Unit Development (PUD) is to provide a flexible approach for development, allows a more flexible response to the market, encourage innovative mixed uses and site plan design.

Background/Issue (What prompted this need?):

The applicant: W.M.F. Investments is requesting the approval of a preliminary Planned Unit Development (PUD) "Chesapeake Bay Luxury Seniors Community". The project will be 55 years of age restricted, 269 unit multifamily development.

The project will be constructed on approximately a 13 acres site located immediately east of Repsdorph and south of Brummerhop Park.

Agenda Briefing Form
Page 2

Impacted Parties (Expected/Notified):

Recommended Action:

Attachments:

Exhibit A. Preliminary Planned Unit Development Plan, Titled "Chesapeake Bay Luxury Seniors Community"

Fiscal Impact:	Budgeted	___ Yes	___ No	Finance Officer Review:
	Budget Amendment Required	___ Yes	___ No	
	Future/Ongoing Impact	___ Yes	___ No	

Budget Dept/Line Item Number N/A

Funding Comments:

N/A

Where on the agenda should this item be placed?

(i.e. Public Hearing, New Business, Old Business, Consent Agenda, Executive Session, etc.)

Joint Public Hearing & New Business

Suggested Motion:

City Manager Review:

- ☐ Approved as submitted
- ☐ Submitted for Council consideration without comment
- ☐ Submitted for Council consideration with comments stated below:

(All items are to be reviewed and approved by the city manager, except items submitted by the mayor or any council member or routine consent agenda items such as minutes and second & third readings of ordinances.)

Sent to City Attorney for review _____
(City Attorney should review all ordinances, resolutions, contracts and executive session items.)

Received and accepted by the City Secretary/Assistant _____

Returned by the City Secretary/Assistant (If incomplete) _____

All requests must be submitted to the City Secretary's Office no later than 5:00 p.m. on the Wednesday preceding the regular Tuesday Council Meeting. All required attachments are to be submitted with the request. Incomplete items cannot be placed on the agenda.

CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



**MUCASEY
&
Associates**
Architects





SCALE: 1" = 100' - 24" x 36" SHEET

CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



PROJECT SUMMARY:

Units:	Type	Description	Qty.	Area
	A1	One Bedroom, 1 Bath	70	729 s.f.
	A2	One Bedroom, 1 Bath	12	746 s.f.
	A3	One Bedroom, 1 Bath (Garage)	24	820 s.f.
	A4	One Bedroom, 1 Bath (Garage)	16	791 s.f.
	Total One Bedroom Units			
			122 Units	
	B1	Two Bedroom, 2 Bath	59	990 s.f.
	B2	Two Bedroom, 2 Bath	32	1,012 s.f.
	B3	Two Bedroom, 2 Bath (Garage)	48	1,098 s.f.
	B4	Two Bedroom, 2 Bath (Garage)	8	1,115 s.f.
	Total Two Bedroom Units			
			147 Units	
	Units Total			269 Units
				244,736 s.f.

J.C. JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS

DATE: 11-24-2014

CHESAPEAKE BAY - A LUXURY SENIORS COMMUNITY




CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



**MUCASEY
&
Associates**
Architects




CHESAPEAKE BAY

A Luxury Seniors Community


Developed by
WMF INVESTMENTS



PARKING SUMMARY	
● Attached Garages	96
● Breezeway Garages	82
● Open Parking	173
Total Parking	351
Minimum 1.3 Spaces/Unit	



TYP. PARKING DETAIL




CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



**MUCASEY
&
Associates**
Architects



OPEN SPACE SUMMARY

 **INDICATES OPEN SPACE**
MINIMUM 20% OPEN SPACE

170,319 SF PROVIDED
29% OF TOTAL SITE AREA



SCALE: 1" = 100' - 24" x 36" SHEET

EXHIBIT B-6

CHESAPEAKE BAY



A Luxury Seniors Community

Developed by
WMF INVESTMENTS



MUCASEY & Associates
Architects

SIGN & SOLID WASTE ENCLOSURE DETAILS



1 Dumpster #2 - Plan
3/4\"/>

2 Dumpster #1 - Plan
3/4\"/>

1 ENTRY SIGNAGE (TYP. EA. FACE)
3/4\"/>

1 Dumpster #1 - Elevation
3/4\"/>

1 Dumpster #2 - Elevation
3/4\"/>

2 DUMPSTER WALL SECTION
3/4\"/>

JC JONES & CARTER, INC.
ENGINEERS-PLANNERS-SURVEYORS

CHESAPEAKE BAY - A LUXURY SENIORS COMMUNITY

DATE: 11-24-2014

CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



**MUCASEY
&
Associates**
Architects



EXHIBIT B-7a:

EXISTING UTILITIES


CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



MUCASEY & Associates
Architects



JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS

DATE: 11-24-2014

CHESAPEAKE BAY - A LUXURY SENIORS COMMUNITY


EXHIBIT B-7b:

EXISTING UTILITIES


CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



MUCASEY & Associates
Architects



J. JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS

DATE: 11-24-2014


CHESAPEAKE BAY - A LUXURY SENIORS COMMUNITY

CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS

 **MUCASEY & Associates**
Architects




CHESAPEAKE BAY

A Luxury Seniors Community


Developed by
WMF INVESTMENTS



**MUCASEY
&
Associates**
Architects





Amenity Center Detail



CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



CHESAPEAKE BAY

A Luxury Seniors Community

Developed by
WMF INVESTMENTS



**MUCASEY
&
Associates**
Architects







EXHIBIT B-10C:

TYPICAL FLOOR PLANS


CHESAPEAKE BAY

A Luxury Seniors Community


Developed by
WMF INVESTMENTS



MUCASEY & Associates
Architects




UNIT "B2" - Two Bedroom, 2 Bath



UNIT "B2" - Two Bedroom, 2 Bath



UNIT "B4" - Two Bedroom, 2 Bath (attached garage)



UNIT "B3" - Two Bedroom, 2 Bath (attached garage)

EXHIBIT B-11
CHESAPEAKE BAY PLANNED UNIT DEVELOPMENT
PRELIMINARY DEVELOPMENT SCHEDULE

- A. Second Quarter 2015: Design and plan review and approval**
- B. Third Quarter 2015: Begin on site construction**
- C. Second Quarter 2016: Construction complete**
- D. Mid 2016: Begin occupancy.**

Exhibit B

CHESAPEAKE BAY PLANNED UNIT DEVELOPMENT DISTRICT PLAN

A. CONTENTS

This Planned Unit Development District Plan (PUD) includes the following Sections:

- General Provisions
- Permitted Land Uses
- Development Regulations
- Building Regulations

B. GENERAL PROVISIONS

1. The PUD approved herein must be constructed, developed, and maintained in compliance with this ordinance and other applicable ordinances of the City. If any provision or regulation of any City ordinance applicable in a R-3(Medium Density) zoning district (Base Zoning) is not contained in this ordinance, all the regulations contained in the Zoning and Subdivision ordinances applicable to the R-3 zoning district in effect on the effective date of this ordinance apply to this PUD as though written herein, except to the extent the City regulation or provision conflicts with a provision of this ordinance.
2. Except as otherwise provided herein, the words used in this PUD have the meaning established by the Zoning ordinance. In this ordinance:

Accessory building means a building subordinate to a principal building and includes detached garages.

Open Space means the portion of all land contained within the PUD that is not covered by buildings, parking lots, driveways, improved pedestrian areas, or other impermeable material.

PUD means the planned unit development district created by this ordinance.

Shared/Common Driveway means a privately owned and maintained vehicular access way that provides access from a public street to residential or non-residential units.

3. The PUD shall be developed in accordance with the following exhibits that are attached to and made part of this document:

Exhibit B-1:	<i>Location Map</i>
Exhibit B-2:	<i>Site Plan</i>
Exhibit B-3:	<i>Access Detail</i>
Exhibit B-4:	<i>Parking Layout</i>
Exhibit B-5:	<i>Open Space Plan</i>
Exhibit B-6:	<i>Sign and Solid Waste Enclosure Details</i>
Exhibit B-7 -- 7a:	<i>Existing Utilities</i>
Exhibit B-8:	<i>Amenity Center</i>
Exhibit B-9:	<i>Building Elevations</i>

Exhibit B10a, b, & c: *Typical Floor Plans*
Exhibit B-11: *Development Schedule*

4. As shown on *Exhibit 1, Location Map*, the PUD encompasses approximately 13.45 acres between West Repsdorph Road to the west, Huckleberry Finn Cove to the east, Lot 1 Repsdorph Partition to the south, and Peeblebrook Drive to the north.
5. Senior Living, age restricted residential development shall substantially conform to the general layout and design concepts illustrated on *Exhibit B-2, Site Plan*.
6. Refuse containers which are to serve multi-family residential uses are not permitted within view of West Repsdorph Road. *Exhibit 6, Sign and Solid Waste Enclosure Details*
7. Signage: a Freestanding sign meeting the City's requirements established in Article 6 – Sign Standards will be constructed on-premises as shown on *Exhibit 6, Sign and Solid Waste Enclosure Details*

C PERMITTED LAND USES

1. Senior Living - Age Restricted Residential, up to 269 units are permitted as shown on *Exhibit B-2, Site Plan*, contingent on the following conditions:
 - a) All residents of the facility must be 55 years of age or older, or the spouse of a resident who is 55 years of age or older.
 - b) The facility shall include a common amenity area of not less than 5,000 square feet, including kitchen facilities, common use meeting rooms and gathering places, and shall substantially conform to the general layout and design concepts illustrated on *Exhibit B-8, Amenity Center*
 - c) The facility shall provide physical fitness / wellness center

D DEVELOPMENT REGULATIONS

1. Maximum height of structures: 3 stories, but no more than 40 feet above ground level except as follows:
 - (a) Chimneys, ornamental tower spires, cooling towers, elevator bulkheads, fire towers, stacks, roof gables, parapet walls, and mechanical equipment may extend an additional Height not to exceed 15 feet above the maximum Height allowed for the Structure to which it is affixed.
 - (b) Satellite Dish Antennas as permitted by the City's accessory use regulations and towers and antennas and permitted by Article VII, regulating telecommunication towers and antennas.
2. All Senior Living - Age Restricted Residential development shall conform to the (R-3) Medium Density zoning district with the following exceptions:

- (a) Off-street parking:
 - i. 1.3 parking spaces is required for each unit of Senior Living - Age Restricted Residential
 - ii. Fifty percent (50%) of the required parking shall be covered or garage parking.
 - (b) Fencing: An 8' high opaque, concrete panel fence will be installed along the south and east boundary of the site. An open style "wrought Iron" metal fence with masonry columns will be constructed along the north and west boundary of the site.
 - (c) Paving:
 - i. All parking lots and vehicle use areas must be constructed of concrete.
 - ii. Driveways may be constructed of concrete, or paved with interlocking, multicolored pavers supported by a 6 inch reinforced concrete tray and a sub-grade per City design standards.
3. Building Area: Not more than 50 percent of the total site area shall be covered by building mass.

E LANDSCAPE AND PEDESTRIAN CIRCULATION REGULATIONS

The PUD shall require the following regulations adjacent to any tracts developed for Senior Living – Age Restricted Residential uses:

- 1. Landscape buffer (Single-family adjacency consideration):
 - (a) 30-foot minimum buffer shall be provided along the eastern property boundary.
- 2. Lighting used to illuminate sidewalks, landscape buffers, bicycle parking areas, or other common open space shall be arranged, located, or screened to direct light away from existing single-family residential lots.
- 3. Sidewalks: Sidewalks are required to connect the front entrance of each unit to the paved parking areas. All sidewalks shall be paved with concrete and be a minimum of four (4) feet wide. Trails extending through landscape and natural areas may be constructed using decomposed granite or other similar material.

F BUILDING REGULATIONS

The PUD shall require the following regulations for Senior Living

Age Restricted Residential Developments:

1. Primary exterior finishes are limited to brick, stone (natural, cast, or cultured-textured), textured concrete panels, glass, and fiber cement siding, cement plaster, and shall comprise at least 70% of each façade.
2. Secondary exterior finishes shall include wood, ceramic tiles, concrete masonry units (indented, hammered, or split face concrete), and stucco, and shall comprise no more than 30% of each façade.
3. Architectural Metals may be used for canopies, parapet walls, roof systems, and miscellaneous trim work.
4. Roofing materials shall be limited to the following:
 - a. Slope roof – dimensional composite shingles, metal, tile
 - b. Flat roof – shall meet the requirements as required by the IBC